BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16541

NEGOTIATION SCHEDULE - B

O.E.E/BTP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014

mprovements to roads at Balaji layout (near Singapura main road and cross roads in ward no. 11 (Kuvempunagara) Vidyaranypaura sub division.

Sl. No.	Approved Qty.	Description	Unit	Negotiation Tender Rates of N THIRUNAGENDRA	
				In Figures	In Words
1	431.28	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	79.37	Rupees Seventy nine thirty seven paise
2	544.1	Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	111.12	One hundred eleven and twelve paise.
3	969.3	Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	61.23	Sixty one & twenty three
4	969.3	Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	79.37	Seventy nine and thirty seven
5	544.1	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1510.34	One thousand five hundred ten and thirty four paise.
6	3627.3	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, etc complete as per specifications and directions of engineer in charge of the work	Sqm	12.81	twelve rupees and eighty one paise
7	3627.3	Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 1.10 Kg/Sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	78.24.	Seventy eight and twenty four.

	Approved Qty.	Description	Unit	Negotiation Tender Rates of N THIRUNAGENDRA	
				In Figures	In Words
8	90.68	Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 508 complete in all respects as per specifications. using 100-120 TPH capacity H.M.P with sensor paver grading II (25-30mm) with 5% CRMB-55 grade, etc complete as per specifications and directions of engineer in charge of the work	Cum	11622-39	Eleven thousand Six hundred twenty two rupees and thirty nine paise.
9	731.53	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. etc complete as per specifications and directions of engineer in charge of the work	Cum	77724	Seventy seven and twenty four paise.

N. Thirunagendra
Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92